



TRACEMORE ESTATES NO. 4

SECTION 30, TOWN 5, RANGE 13, LIBERTY TOWNSHIP, LOGAN COUNTY, OHIO



DESCRIPTION

LYING IN SECTION 30, TOWN 5, RANGE 13, LIBERTY TOWNSHIP, LOGAN COUNTY, OHIO.

BEING OUT OF THE PAUL T. HUMBLE AND LOIS J. HUMBLE ORIGINAL 17.78 ACRE TRACT AS DEEDED AND DESCRIBED IN OFFICIAL RECORD 21, PAGE 921 AND ALL OF THE REMAINDER OF THE ORIGINAL 44.57 ACRE TRACT AS DEEDED AND DESCRIBED IN OFFICIAL RECORD 84, PAGE 949 OF THE LOGAN COUNTY RECORDS OF DEEDS AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT A 5/8 INCH IRON ROD FOUND AT THE SOUTHWEST CORNER OF TRACEMORE ESTATES NO. 2 (PLAT CABINET A, SLIDES 723A & B, 725A).

THENCE, WITH THE SOUTH LINE OF TRACEMORE ESTATES NO. 2 AND THE SOUTH LINE OF TRACEMORE ESTATES NO. 3 (PLAT CABINET B, SLIDES 288 & 29A), S 85°-47'-58"E, A DISTANCE OF 1218.17 FEET TO A 5/8 INCH IRON ROD FOUND.

THENCE, WITH THE LINES OF TRACEMORE ESTATES NO. 3, THE FOLLOWING TWO COURSES:

S 4°-12'-01"W, A DISTANCE OF 100.15 FEET TO A 5/8 INCH IRON ROD FOUND.

S 85°-51'-48"E, A DISTANCE OF 374.94 FEET TO A 24" OAK TREE FOUND, PASSING 5/8 INCH IRON RODS FOUND AT 60.00 FEET AND 372.33 FEET.

THENCE, WITH THE WEST LINE OF THE THOMAS A. WHITE 14.57 ACRE TRACT (VOL. 374, PG. 752), S 6°-23'-15"W, A DISTANCE OF 64.80 FEET TO A 3/4 INCH IRON ROD FOUND.

THENCE, S 32°-04'-25"W, A DISTANCE OF 238.56 FEET TO A 5/8 INCH IRON ROD FOUND.

THENCE, S 4°-06'-37"W, A DISTANCE OF 179.92 FEET TO A 5/8 INCH IRON ROD FOUND.

THENCE, WITH THE LINES OF TRACEMORE OAKS ALLOTMENT (PLAT CABINET A, SLIDES 595-597), THE FOLLOWING ELEVEN COURSES:

COVENANTS AND RESTRICTIONS


ARTICLE I

- (A) **LAND USE:** All of said lots in TRACEMORE ESTATES NO. 4 shall be used for single family residential purpose only. All garages shall be attached to the residence building and no unattached permanent structures of any type or other out-buildings shall be constructed or erected on any lot unless the building is in general conformity with the residence architecture, the size exceeds 400 square feet, the size does not exceed 1200 square feet. The word, architecture, in the preceding sentence refers to all aspects of appearance such as exterior treatment, roof slope, and landscaping.
- (B) **HEIGHT RESTRICTIONS:** No building shall be erected, altered, placed, or permitted to remain on any lot that would exceed two and one half stories in height and in no event shall any building be erected to a height exceeding 35 feet from the finish grade of the building, together with necessary accessory buildings including a garage.
- (C) **LOT SPLIT:** No lot shall be split, divided, or subdivided for sale, resale, gift, transfer or otherwise, so as to create a new building lot.
- (D) **TRADE OR COMMERCIAL ACTIVITY BARRED:** No trade or commercial activity shall be conducted upon any lot, nor shall anything be done thereon which may become an annoyance or nuisance to any of the owners of any said lot in TRACEMORE ESTATES NO. 4.
- (E) **BUILDING STANDARDS:** All homes constructed on lots in TRACEMORE ESTATES NO. 4 shall meet and conform to the following requirements:
 - (1) A minimum living space of 1,800 square feet except for Lot #14 which may have a minimum living space of 1,600 square feet.
 - (2) Two car attached garages comprising a minimum of 550 square feet.
 - (3) Exterior material of stone, brick, cedar, redwood, other solid natural woods, stucco, vinyl siding up to 50% of exterior, or a form thereof, or combinations thereof.
 - (4) Minimum roof pitches, 5 units vertical to 12 units horizontal.
 - (5) Mandatory use of architectural or "dimensional" shingles.
 - (6) Mandatory use of earth tones and muted colors on painted surfaces with the exception of architectural accents.

NOTE:

THIS PLAT CONSISTS OF TWO (2) PAGES, AND BOTH PAGES MUST BE USED FOR A COMPLETE REPRESENTATION OF THIS SUBDIVISION.

- (K) **LOT MAINTENANCE AND WASTE DISPOSAL:** No lot shall be used or maintained as a dumping ground for rubbish. Trash, garbage, or other waste shall not be kept except in sanitary containers. All equipment for the storage or disposal of such material shall be kept in a clean and sanitary condition and kept within the confines of the owner's dwelling. On trash removal day, trash containers may be kept on driveways or streets for a maximum period of 24 hours. All developed lots with or without residences shall be maintained by the owner of said lots by mowing no fewer than two times each year, not later than June 14 and September 1.
- (L) **VEHICLES NOT IN USE:** No automobile or motor driven vehicle shall be left upon any lot for a period longer than 10 days in a condition wherein it is not able to be operated upon the public highway. After such period, the vehicle shall be considered a nuisance and detrimental to the welfare of the above described real estate and shall be removed therefrom.
- (M) **HOBBIES:** Hobbies or other activities which tend to detract from the aesthetic character of TRACEMORE ESTATES NO. 4 and any improvements used in connection with such hobbies or activities shall not be permitted unless carried out or conducted within the building erected upon the lot and not viewable from either the street or adjoining properties. This restriction refers specifically but not exclusively to such activities as automobile, bicycle, moped, motorboat and sailboat repair.
- (N) **BOAT, TRAILER, AND VEHICLE PARKING AND STORAGE:** No truck, trailer, boat, camper, recreational vehicle or commercial vehicle shall be parked or stored on any lot unless it is in a garage or other permanent vehicle enclosure out of view from the street and adjoining properties; provided, however, that nothing herein shall prohibit the occasional non-recurring temporary parking of such truck, trailer, boat, camper, recreational vehicle or commercial vehicle on the premises for a period not to exceed 72 hours in any period of thirty (30) days.
- (O) **SIGNS:** No signs of any kind shall be displayed to the public view, on any lot, except one temporary sign of not more than six square feet advertising the property for sale or rent, or signs used by the builder to advertise the property during the construction sales period.
- (P) **ANTENNAS:** Radio antennas, including satellite dishes larger than 2 meters, whether roof-top or ground mounted, shall be prohibited on the exterior of any house or lot. Satellite dishes not exceeding 2 meters in diameter are acceptable.
- (Q) **EASEMENT:** No permanent structures or plantings, etc., shall be permitted within the easement area. Easement areas are for all public utilities. The easement is for the use of the public utility companies for the installation of those utilities.
- (R) **GRADING AND DRAINAGE:** No construction, grading or other improvements shall be made to any lot if such improvement would interfere with or otherwise alter the general grading and drainage plan of the subdivision or any existing swales, floodways, or other drainage configurations.
- (S) **EXPOSED BLOCK:** No buildings or structures within the subdivision may have more than two (2) courses of exposed block.



N 85°-50'-37"W, A DISTANCE OF 1130.16 FEET TO A 5/8 INCH IRON ROD FOUND.

N 3°-46'-24"E, A DISTANCE OF 12.81 FEET TO A 5/8 INCH IRON ROD FOUND.

N 85°-48'-22"W, A DISTANCE OF 282.91 FEET TO AN ELECTRIC TRANSFORMER FOUND, PASSING 5/8 INCH IRON RODS SET AT 51.85 FEET AND 278.91 FEET.

N 4°-07'-29"E, A DISTANCE OF 169.66 FEET TO A 5/8 INCH IRON ROD FOUND, PASSING A 5/8 INCH IRON ROD SET AT 4.00 FEET.

N 83°-44'-44"W, A DISTANCE OF 51.58 FEET TO A 5/8 INCH IRON ROD SET.

WITH A CURVE TO THE LEFT, HAVING A CENTRAL ANGLE OF 91°-46'-28", A RADIUS OF 121.60 FEET, AN ARC LENGTH OF 194.77 FEET, A CHORD BEARING OF S 50°-02'-21"W, A CHORD DISTANCE OF 174.61 FEET TO A 5/8 INCH IRON ROD SET.

S 4°-09'-23"W, A DISTANCE OF 156.16 FEET TO A 5/8 INCH IRON ROD SET.

N 84°-15'-48"W, A DISTANCE OF 60.26 FEET TO A 5/8 INCH IRON ROD FOUND.

N 4°-08'-55"E, A DISTANCE OF 155.07 FEET TO A 5/8 INCH IRON ROD FOUND.

N 85°-09'-12"W, A DISTANCE OF 240.03 FEET TO A 5/8 INCH IRON ROD FOUND.

N 4°-14'-17"E, A DISTANCE OF 172.67 FEET TO A TELEPHONE PEDESTAL FOUND, PASSING A 5/8 INCH IRON ROD SET AT 170.67 FEET.

THENCE, WITH THE LINES OF THE JEFFREY L. REYNOLDS 2.15 ACRE TRACT (VOL. 405, PG. 771), THE FOLLOWING THREE COURSES:

S 86°-36'-30"E, A DISTANCE OF 426.73 FEET TO A 6" WOOD POST FOUND, PASSING A 5/8 INCH IRON ROD SET AT 2.00 FEET.

N 5°-48'-45"E, A DISTANCE OF 143.40 FEET TO A 6" WOOD POST FOUND.

N 81°-16'-28"W, A DISTANCE OF 20.84 FEET TO A 2 INCH IRON PIPE FOUND.

THENCE, WITH THE EAST LINE OF THE JEFFREY L. REYNOLDS ORIGINAL 15.853 ACRE TRACT (O.R. 12, PG. 303) N 4°-33'-10"E, A DISTANCE OF 166.62 FEET TO THE POINT OF BEGINNING.

CONTAINING 19.949 ACRES.

(F) **PLAN APPROVAL:** For the purpose of maintaining specific architectural guidelines and standards for the development of all said lots within TRACEMORE ESTATES NO. 4, each owner of a lot shall be required to submit (2) sets of preliminary building and site plans with specifications for the buildings intended to be erected thereon to the Grantor, setting forth the general arrangements of the interior and exterior of the structure, including the color and texture of the building materials, the type and character of all windows, doors, exterior light fixtures and appurtenant elements such as decorative walls, chimneys, driveways and walkways and detailing the location of the structure on the lot including setbacks, driveway locations, garage openings, orientation of the structure to the topography with the grading and drainage plan.

Each owner covenants that no excavations shall be made, no building shall be erected and no materials shall be stored upon the premises by said owner or his agents, heirs, successors, or assigns until the Grantor shall have approved said plans and specifications in writing. If the Grantor fails within ten (10) days after receipt of said plans and specifications to either approve or disapprove said plans and specifications, they shall be deemed to have been approved and the requirements herein fulfilled. If the Grantor disapproves said plans and specifications, the owner may revise and resubmit said plans and specifications until approval is received.

Each lot owner further acknowledges that in considering plans and specifications submitted, Grantor will take into consideration plans and specifications already approved or the process of being reviewed for approval of proposed improvements on adjacent lots and the effect upon the neighboring properties and the overall development of TRACEMORE ESTATES NO. 4. As a general principal, the Grantor will not approve plans that are identical or closely approximate to those that have been previously submitted for review and approval. Each lot owner further acknowledges that the Grantor shall not be responsible or liable to said owner or to any other owner of lots in the subdivisions by reason of the exercise of its judgment in approving or disapproving plans submitted nor shall it be liable for any expenses entailed to any lot owner in the preparation, submission and, if necessary, resubmission of the proposed plans and specifications. No homes of unusual appearance in style to the area shall be permitted such as "dome" homes, buried homes, or A-frame structures.

Each lot owner further agrees that no free removal, excavation, construction or other site work which would in any way alter the lot from its present state shall be commenced until the plans and specifications shall first have been approved in writing by Grantor in accordance herewith.

Within the easement areas designated on the recorded plat of TRACEMORE ESTATES NO. 4, no structure, planting or other material shall be placed or permitted to remain which may damage or interfere with the installation and the direction of the flow of the drainage channels or water over said easement areas. The easement area of each lot and all surface improvements thereon shall be maintained continuously by the owner of said lot, except for those improvements for which a public authority of a public utility company is responsible.

- (G) **BUILDING LOCATION; FENCES:** Unless an exception is approved by Grantor, no building shall be located on any lot nearer to a side street than the minimum building setback lines shown on the recorded plat or nearer to the rear property line than thirty feet. No portion of any lot nearer to any street than the building setback lines shall be used for any purposes other than that of a lawn nor shall any fence or wall of any kind, for any purpose, be erected, placed or suffered to remain on any lot nearer to any street now existing, or any hereafter created, than the front building lines of the building thereon, excepting ornamental railing, or fences not exceeding four (4) feet in height located on or adjacent to entrance platforms or steps. This provision (G) shall be applicable to limit the size or location of the subdivision entry signs, identification or walls. Nothing herein contained, however, shall be construed as preventing the use of such portions of the lots for walks, drives, the planting of trees or shrubbery, the growing of flowers or other ornamental plants, or for small statuary entranceways, fountains or similar ornamentals for the purpose of beautifying said premises. No vegetable, or grains of any variety shall be grown on such portions of said lots for commercial sale, and no weed, underbrush or other unsightly growths shall be permitted to grow or remain anywhere on said lots and no unsightly objects shall be allowed to be placed or suffered to remain anywhere thereon. No restriction is placed on the planting and tending of private gardens for personal use in rear yard. Nothing herein contained shall be construed so as to permit a violation of any applicable law, ordinance or governmental regulation.

No chain link fencing or common agricultural fencing shall be permitted in the subdivision.

- (H) **RESIDENCE:** No structure of a temporary character, trailer, basement, tent, shack, garage, barn, or other outbuilding shall be used on any lot at any time as a residence either temporarily or permanently.

- (I) **TEMPORARY STRUCTURE:** No temporary building, trailer, garage, storage building shall be placed upon any lot for storage without the express written consent of Grantor.

- (J) **ANIMALS:** No animals, birds, insects, livestock or poultry of any kind shall be raised, bred, or kept on any lot except dogs, cats, or other household pets which are kept for domestic purposes only, and are not kept, bred, or maintained for any commercial purpose. No more than two dogs or two cats may be kept on any lot except such dogs or cats in excess of such numbers that are less than three months of age. All animals must be restrained on the owner's lot or on a restraining leash or electric restraint and owners shall take all steps to insure the same.

2 WORKING DAYS
BEFORE YOU DIG
 CALL TOLL FREE 800-362-2764
 OHIO UTILITIES PROTECTION SERVICE.

ARTICLE II
 Grantor reserves the right to modify or amend these Deed Restrictions during the period of constructing improvements and selling all lots. However, any modification or amendment shall not further restrict those requirements set forth herein.

ARTICLE III

- (A) These restrictions shall run with the land and shall be binding upon all parties until 2017, after which said restrictions shall be automatically extended for successive periods of ten years unless an instrument signed by a majority of the then owners of the lots in said subdivision has been recorded, agreeing to change said restrictions in whole or in part.
- (B) Enforcement of these restrictions shall be by proceedings at law or equity against any person or persons violating or attempting to violate any restriction, either to restrain any violation or to recover damages including attorney fees and court costs.
- (C) Invalidation of any one of these restrictions by judgment of court shall in no way affect any of the other provisions which shall remain in full force and effect.