


72 10th mo. (Oct) 26th 1827 ✓ Survey no. 87 (8213)


Surveyed for Martin Shields and others; Beginning at a stake in the road leading from West-Liberty to Bellefontaine, where the east line of section 24 in Town. 5 Range 13 N.W. 1/4. crossing said road, also at the South east corner of the north east quarter of said section; thence north $37\frac{1}{2}$ poles to a stake a few feet South of a black oak bush; thence west, $\frac{1}{2}$ westerly variation, crossing said road at 32 poles, 170 poles, a white oak 170° N 10 links a white $63^{\circ} 6'$ 17 links; thence $63^{\circ} 6'$ poles, a black oak south 12 links; thence east $\frac{1}{2}$ westerly variation 170 poles to the beginning containing forty acres off of the south side of the south east q. sec 24 Town 5 Range 13 N.W. 1/4.



Ja. Williamson
S. L. C.

10th mo. (Oct) 27th 1827 ✓ Survey no. 88 (8214)

Surveyed for Joseph McBeth; Beginning at the south east corner of section 35 in Town. 5 Range 13 N.W. 1/4. a white oak 20 inches in diam. $\pm 40^{\circ} 6'$ 14 links dist. a white oak 130° N 25 links; thence north $37\frac{1}{2}$ poles to a large forked white oak; thence west ($\frac{1}{2}$ westerly variation) 170 poles; thence south $67\frac{1}{2}$ poles to a large white oak in the south line of the section; thence with said line east ($\frac{1}{2}$ variation) 170 poles to the beginning containing 40 acres off the south side of the south east quarter of said section.



Ja. Williamson S. L. C.

10th mo. (Oct) 27th 1827 ✓ Survey no. 89 (8214)

Surveyed for Joseph McBeth; Beginning at a stake north west corner to the above survey no. 88; thence north 120 poles to a stake in the center of Sec. 35 Town 5 Range 13; thence east ($\frac{1}{2}$ variation westerly) 79.3 poles; thence west to a large oak